



HMRC Dorset House Information Centre

Client: HMRC

Site: London

Work undertaken: Partition
Alterations

Value: £3,500.00.

Work period: 4 Days (Out of
hours)



**SOUTH
ANSTON**



Problem:

We were advised that there were problems with the Administration staff one side of a partitioning wall being unable to observe the general public and the operatives advising the general public.

This was due to the existing height of the partition wall in relation to the glass window inserts.

Solution:

To lower the last section of partition wall and install a larger piece of glass partitioning.

Main Consideration:

To match existing structure and blend décor.

The logo for South Anston, featuring the word "SOUTH" in a bold, black, sans-serif font above the word "ANSTON" in a bold, white, sans-serif font, which is set against a solid black rectangular background.

Specifications:

1. Remove 1 single pane of glass from each side of the partition wall.
2. Cut away existing plasterboard to open up the existing wall.
3. Strengthen new lower lever wall.
4. Make good reveals and returns.
5. Tape and joint all new plasterboard.
6. Redecorate.
7. Supply and install 2 new glass panels to match existing complete with channelling.

**SOUTH
ANSTON**

“Work was carried out over 2 weekends. On completion the client found this solution extremely beneficial. It catered for all their needs and resolved the problem”

**SOUTH
ANSTON**